

CalStyleRoofingContract[1]

Roofer: Califomill style Roofing
164 Harian Ln., San Jose, Ca. 95127
Lic.# 777826 C39

Owner, Felix: 408-401-4935
Consulting: Lorenzo: 408-592-4596
Email: calstyleroofing@yahoo.com

Contract #: CSR723
Date: June 15, 2011

New 2 story House with 2 car garage detached
Job address: 470 Ruthven Ave., Palo Alto, CA 94301-1222

Customer: owner-Builder: Fatekh Vergasov
e-mail: fv1946@sbcglobal.net
phone: 650-465-3773 cell

Contract

Scope of works, materials and services includes:

Main house:

- A. Install one layer of felt #30 Ibs. ASTM asphalt saturated roofing underlayment with 3/4" plastic top nails.
- B. Install one layer of # 72 Ibs cap sheet granulated mineral surface with 3/4" plastic top nails.
- C. Install two pieces U S clay tile (blended colors) on roof with 1 1/2 roofing nail per manufacturer specifications. *EL CAMINO F.V. F.D. 0906-0010*
- D. Install bird stop on first course with 1 1/4" roofing nail.
- E. Install all new-galvanized pipe flashing, heat vents on first underlayment of felt to make water tie.
- F. Install new pipe flashing with lead, heat vents with lead, new-galvanized tile pan, and valleys for tile.
- G. Install approx, 10 low profile O'Haggins vents
- H. Install wood 2x6 on all hips and ridge to install the ridge tile.
- I. Install new saddle flashing with lead on 2 chimneys and skylights.
- J. Install roof to wall with lead on first story, including material and labor.
- K. Install mortar with color (matching the color of the tile) underneath of the tile on all hips and ridges.
- L. Install rubber collar on all pipe jacks.
- M. Install two saddles metal with lead for skylights.
- N. All metal flashing to be painted with rust preventing paint matching the color of the roof.
- O. Carefully inspect all ground after finished all work to clean up all roof related debris.

Gutters and downspout:

- A. Install approx. 280 ft of new gutter 5 inches O.G. seamless aluminum painted and approx. 20 downspouts.

Flat area deck (Master BR Balcony):

- A. Install sicaflex on all joints of plywood and metal.
- B. Install one layer of polydeck on top of the plywood.
- C. Install light layer of polydeck to install sand and let them ready for tile
- D. Install Red clay tile

Flat area entry:

- A. Install ice and water shield on top of the plywood

Fatekh Vergasov
07-15-11
Fatekh
VERGASOV

- B. Install galvanized metal 26 gauges
- C. Paint the metal with rust preventing.

Two car garage:

- A. Install one layer of felt #30 Ibs. ASTM asphalt saturated roofing underlayment with 3,4" plastic top nails.
- B. Install one layer of # 72 Ibs cap sheet granulated mineral surface with 3/4" plastic top nails.
- C. Install two pieces U S clay tile (blended colors) on roof with 1 1/2 roofing nail per manufacturer specifications.
- D. Install bird stop on first course with 1 1/4" roofing nail.
- E. Install approx. two low profile Q'Haggins vents.
- F. Install wood 2x6 on all hips and ridge to install the ridge tile.
- G. Install mortar with color (matching the color of the tile) underneath of the tile on all hips and ridges.
- H. Carefully inspect all ground after finished all work to clean up all roof related debris.

Warranty provision:

Califomill style Roofing guarantees all workmanship for Ten (10) years from the day of completion

Other conditions:

1. Roof shall meet requirements of City of Palo Alto
<http://www.cityofpaloalto.org/civica/filebank/blobdload.asp?BlobID=18820>
2. What is omitted, not mentioned or straightly assign to Customer, is 100% responsibility of the Roofer

Price:

Main House: \$20,000.00 (Twenty thousand)
 Garage: \$2,000 (Two thosand)
 Flat area deck (Master BR Balcony) waterproofing: \$600
~~Flat area deck (Master BR Balcony) clay tile installation: ?~~ F.V.
 Gutters and downspouts installation at both Garage and main house: \$2,000 (Two thosand)
 Flat area entry portion of the roof: Free

Total: 24,600 - F.I. (Twenty four thousand six hundreds)

Paiment schedule: F.V.

Downpayment - no
 Underleyer installed - \$2,500 (Two thousand five hundred)
 Clay tile delivered and stored at the roofs - 100% cost Reimbursement
 Balance upon installation done

Rofer: [Signature] Felizardo Inzenza
 July 15 2011

Customer: [Signature] Fatakh Vega
 July 15 2011